KOLAR DISTRICT.

Short Notice dated 30th September 1907.

The attention of the public is hereby invited to the Notification dated 30th September 1907, published on pages 1126 and 1127 Part II of the *Mysore Gazette*, dated 10th October 1907 advertising the sale of minor forest products in the Kolar District for 1907-08.

S. A. BAPU RAO,
Dt. Forest Officer.

MYSORE DIVISION.

Dated 19th October 1907.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th November 1907, for constructing servants' quarters in the compound of the Government House at Mysore.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1908.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred only in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing servants' quarters in the compound of the Government House at Mysore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	*Description of work.*	*Per*	*Quantity.*
1	Earth-work, excavation	C. yd.	199
2	Burnt brick in mortar	C. ft.	15,143
3	Burnt brick in clay	Do	1,116
4	Plastering with mortar	Sqr.	195·78
5	Burnt stone slabs dressed 4" thick	S. ft	402
6	Armoured concrete work	C. ft.	265
7	Roofing with Cuddapah slabs and two layers of flat tiles and plastering with chunam	Sqr.	46·54
8	Teakwood doors battened	S. ft.	360
9	Teakwood windows with iron bars	Do	99
10	Chocolate painting	Sqr.	11·91
11	Whitewashing	Do	120·12
12	Color-washing	Do	47·48
13	Flooring with concrete and smoothing	C. ft.	1,388
14	Cornice work including plastering	Rft.	171¾
15	Gravelling with consolidation	C. yd.	43
16	Bond slabs including fixing	Each	32
17	Dismantling old structure, etc,	Lump sum.	
18	Coping with burnt brick in mortar and plaster over	Rft.	214
19	Teakwood gate and iron fittings	S. ft.	40
20	Providing Harburry's patent latrine of three sets of four seats	Each	3
21	Railway charges and fittings, etc.	Lump sum.	
22	Scaffolding and centering charges of armoured concrete work and lifting Cuddapah slabs, etc.	Do	
23	Concrete flooring with cement coating for three sets	Each	3
24	Making holes for inserting joists, etc., and repairs	Lump sum.	

B. SUBBA RAO,
Exec. Engineer.